



Part of Lot 1, CSM 6807, being located in part of the Southeast 1/4 of the Northeast 1/4, Section 9, Township 21 North, Range 17 East, Town of Grand Chute, Outagamie County, Wisconsin

White Hawk Meadows North 4





# LEGEND

- △ 1¼" Rebar Found
- o 3/4" Rebar Found
- 1¼" x 18" Steel Rebar @ 4.30lbs/LF SET All other corners

3/4" x 18" Steel Rebar @ 1.50lbs/LF SET

### **Special Town of Grand Chute Restriction**

The final plat is subject to all of the requirements of § 475-15E of the Code of the Town of Grand Chute. The subdivider, for himself and his assigns, shall be responsible for all municipal improvements, including asphalt surface streets, graveled road shoulders or curb and gutter, sewer and water, sewer lift stations, storm sewers, dedicated clear water drainage easements, and streetlighting. Pursuant to § 475-15E of the Code of the Town of Grand Chute, the Town of Grand Chute reserves the right to withhold building permits for this subdivision if the above-stated municipal improvements have not been completed by the subdivider according to the terms and conditions of § 475-15E. Utility Connection Fees (as listed on the Town Fee Schedule) for sewer, water and storm services shall be payable by each lot within the platted subdivision to the Town of Grand Chute Sanitary Districts. A special streetlighting charge, in accordance with the procedures listed under § 57-21, Special charges for current services, shall be assessed annually to property owners of each buildable lot within the subdivision for the energy and facility maintenance costs of streetlighting within the Town. Any costs due to streetlighting in excess of the standards within the Street Lighting Policy, as requested by the subdivider or property owners, shall be assessed directly to the abutting property owners.

There is an impact fee due on each lot in accordance with Chapter 330 Impact Fees of the Town Code of Ordinances and as listed on the most current Town of Grand Chute Impact Fee Schedule.

### **Lot Grading, Staking and Easements**

- 1. The land on all side and rear lot lines of all lots shall be graded by the property owner and maintained by the abutting property owners to provide for adequate drainage of surface water.
- 2. Each lot owner shall grade the property to conform to the lot line grades established by the drainage plan for White Hawk Meadows North. It is the responsibility of the lot owner to comply with these established elevations.
- 3. No poles, pedestals, transformers or buried cable are to be placed within two (2) feet of any survey stake, or placed so as to obstruct vision along any lot line or street line. Any disturbance of a survey stake by any person is a
- 4. Utility easements as herein set forth are for the use of public bodies and private utility providers having the right to serve the area.

## **Stormwater Facility Maintenance Note**

Maintenance of all drainage ways, including easements as indicated on the plat and along side and rear lot lines that convey stormwater runoff in accordance with the approved Drainage Plan, and associated structures within the land division or serving the land division, is the sole responsibility of the property owners of the land division, unless noted on the plan. Upon failure of property owners to perform maintenance of the drainage ways and associated structures within the land division or serving the land division, the Town of Grand Chute and/or Outagamie County retains the right to perform maintenance and/or repairs. The payment of the maintenance and repairs shall be assessed in equal amounts to the owners of all property within the land division, or, where the causer can be specifically identified, the payment shall be assessed to a specific property owner.

Unless otherwise noted, a drainage easement exists upon all existing navigable streams, between the meander lines as

No structures, fences or plantings other than grasses shall be allowed within the drainage easements herein set forth.

# **Geotechnical Study Statement**

A Report of Geotechnical Exploration, RVT #AG03-205, dated October 27, 2003 is on file. This report makes general recommendations based on site conditions for pavements and foundations.

Lot 112 will not be granted access on to Wren Drive.

## Planting Easement:

Lots 96-109 contain a Planting Easement for the sole purpose of planting trees and shrubs to form a buffer along the rail road right of way. Building of structures in the easement is prohibited.

All linear measurements have been made to the nearest one hundredth of a foot.

2. All angular measurements have been made to the nearest 20 seconds and computed to the nearest half seconds.

CURVE TABLE							
Curve	Radius	Chord Direction	Chord Length	Arc Length	Central Angle	Tangent Bearing-in	Tangent Bearing-out
C1	60.00'	N 01°25'17" W	66.05'	307.05'	293°12'37"	S 31°58'25" W	S 34°48'58" E
C2	60.00'	N 73°18'12" W	74.68'	80.61'	76°58'28"	S 68°12'34" W	N 34°48'58" W
C3	60.00'	S 45°51'29" W	45.63'	46.81'	44°42'10"	S 23°30'24" W	S 68°12'34" W
C4	60.00'	S 01°03'09" W	45.83'	47.03'	44°54'29"	S 21°24'06" E	S 23°30'24" W
C5	60.00'	S 43°45'09" E	45.63'	46.81'	44°42'08"	S 66°06'13" E	S 21°24'06" E
C6	60.00'	N 72°56'06" E	78.67'	85.79'	81°55'22"	N 31°58'25" E	S 66°06'13" E
C7	67.00'	S 45°32'45" W	95.09'	105.73'	90°24'47"	S 00°20'21" W	N 89°14'51" W
C8	60.00'	N 45°32'45" E	85.16'	94.68'	90°24'48"	S 89°14'50" E	N 00°20'21" E
C9	60.00'	N 77°32'10" E	27.44'	27.68'	26°25'59"	S 89°14'50" E	N 64°19'11" E
C10	60.00'	N 32°19'46" E	63.57'	67.00'	63°58'50"	N 64°19'11" E	N 00°20'21" E
C11	60.00'	S 44°26'26" E	84.53'	93.79'	89°33'35"	S 89°13'14" E	S 00°20'21" W
C12	60.00'	S 65°34'53" E	48.12'	49.51'	47°16'41"	S 89°13'14" E	S 41°56'33" E
C13	60.00'	S 20°48'05" E	43.28'	44.28'	42°16'54"	S 41°56'32" E	S 00°20'21" W
C14	67.00'	S 44°26'26" E	94.39'	104.73'	89°33'35"	N 35°19'34" W	S 00°20'21" W





Department of Administration

File: 2968Final4.dwg Date: 08/03/2017 Drafted By: jim

Sheet: 1 of 2

Northeast Corner

Lot 2 CSM 2280

S 89°11'37" E 503.62'

12,158 SF

Setback

Easement

12,068 SF

12' Utility

87.00'

20' Drainage Easement 222.88'

20,898 SF

Section 9, T21N, R17E

Masonry Nail Found