

PROPOSED MOUND SYSTEM  
 2 - 3' x 100'  
 CELLS 12' SPACING  
 OUTSIDE DIMENSIONS  
 APPROX. 45'X125'

PROPOSED MOUND SYSTEM  
 2 - 3' x 100' CELLS  
 12' SPACING  
 OUTSIDE DIMENSIONS  
 APPROX. 45'X125'

PROPOSED MOUND SYSTEM  
 3' x 200' CELL  
 OUTSIDE DIMENSIONS  
 APPROX. 40'X22'

Sump pump discharge location Typ. 704.9

Date of Survey: Oct 29, 2018  
 Water Elevation 671.1  
 High Water Mark 674.29

Date of Survey: Nov 7, 2018  
 Water Elevation 686.8  
 High Water Mark 688.7

**BENCHMARKS** (NAVD 88)

BM	Description	Elev
BM 0	NGS PID DE 7707 East side of N. Port Washington 2400 feet North of W. Bonniwell Road	682.35
BM 1	Nail in Powerpole West side of Riverland Road 2030 feet North of Bonniwell Road	702.30
BM 2	Nail in Powerpole West side of Riverland Road 1650 feet North of Bonniwell Road	687.96
BM 3	Nail in Powerpole West side of Riverland Road 1250 feet North of Bonniwell Road	688.02

Driveway	Culvert	Watershed	% Basin	25yr flow to Culvert	Required Size
Lot 1	2C	2.50%	0.84	15	
Lot 2	2C	4.45%	1.49	15	
Lot 3	2C	2.53%	0.85	15	
Lot 4	2C	3.78%	1.27	15	
Lot 5	2B	1.07%	0.25	15	
Lot 6	2B	3.39%	0.80	15	
Lot 7 & Trail	2B	11.26%	2.65	15	
Lot 8	2B	32.23%	7.57	21	
Lot 9	2B	18.88%	4.44	18	
Lot 10	2A	16.81%	1.85	15	
Lot 11	2A	44.17%	4.86	18	
Lot 12	2A	82.91%	9.13	21	
Lot 13 *	2A	96.59%	10.63	24	
Lot 13	2E	22.22%	0.34	15	

\* If driveway is west of the cross culvert

**NOTES:**

- Construction lot pads shall be graded 12" to 18" below finished yard grade. Construction lot pad elevation shall be determined by the developer/engineer based on the amount of basement spoil to be generated by each house.
- Fill areas shall be compacted in one foot lifts to 95% of the modified proctor. A soil testing firm, selected by the City, paid by the developer shall check compaction during the entire filling operation. At the end of the filling operation the soil testing firm shall submit a final certification report to the City Engineering Department.
- No topsoil shall be removed from the site without prior approval by the City Engineer.
- Organic material shall be removed and stockpiled prior to placing structural fill.
- The minimum depth of topsoil shall be four (4) inches.
- Filling operations requiring three or more feet of fill (measured from structural material below topsoil) shall require construction observation during placement.
- Excavated basement spoil material shall not be placed any closer than ten (10') feet to lot corner or lot lines.
- Do not disturb existing ground around proposed septic areas. Mound locations shall be staked prior to grading/excavation to prevent disturbance to septic areas.
- All sump pumps shall discharge into road ditches. Sump pump discharge locations shown are approximate and are to be confirmed by the builder.


**DRAINAGE PLAN CERTIFICATION:**

I, John R. Davel, Professional Engineer, hereby certify that this Drainage Plan will meet or exceed the requirements of the City of Mequon.

John R. Davel, P.E. E-25512 Date \_\_\_\_\_

**LEGEND**

- Proposed Storm Sewer
- Proposed Contour
- Proposed Swale
- Proposed Culvert
- Adjacent Plat Grade
- Prop. Lot Corner Elevation
- Proposed Spot Elevation
- Existing Grade
- Proposed Storm Manhole
- Proposed Curb Inlet
- Prop. Catch Basin / Yard Drain
- Proposed Endwall
- Proposed Rip Rap
- Prop. Drainage Direction
- Prop. Grade at Foundation



**DRAINAGE & GRADING PLAN**

**Riverland Estates**  
 City of Mequon, Ozaukee County, WI  
 For: KKD, LLC